



Regional Commuter Flows Report

September 2022

Wichita Area Metropolitan Planning Organization

271 W 3rd St., Suite 208, Wichita, KS 67202-1212

Office: (316) 779-1313 | Fax: (316) 799-1311

wampo@wampo.org | www.wampo.org

The Wichita Area Metropolitan Planning Organization (WAMPO) hereby gives public notice that it is the policy of the agency to assure full compliance with Title VI of the Civil Rights Act of 1964, the Civil Rights Restoration Act of 1987, Executive Order 12898 on Environmental Justice, Executive Order 13166 on Limited English Proficiency, and related statutes and regulations in all programs and activities.

Title VI requires that no person in the United States of America shall, on the grounds of race, color, or national origin, be excluded from the participation in, be denied the benefits of, or be otherwise subjected to discrimination under any program or activity for which WAMPO receives federal financial assistance. Requests for special accommodation and/or language assistance should be made to wampo@wampo.org or by calling 316.779.1313.

Any persons who believe they have been aggrieved by an unlawful discriminatory practice under Title VI has a right to file a formal complaint with WAMPO. Any such complaint must be in writing and filed with WAMPO's Title VI Coordinator within one hundred eighty (180) days following the date of the alleged discriminatory occurrence. For more information, or to obtain a Title VI Discrimination Complaint Form, please visit www.wampo.org or call 316.779.1313.

Disclaimer: The preparation of this report has been financed in part through funds from the Federal Highway Administration and Federal Transit Administration, U.S. Department of Transportation, under the Metropolitan Planning Program, Section 104(f) of Title 23, U.S. Code. The contents of this report do not necessarily reflect the official views or policy of the U.S. Department of Transportation.

Contents

Introduction.....	4
WAMPO Planning Boundary.....	5
Wichita	9
Derby.....	12
Andover.....	15
Haysville.....	18
Park City.....	21
Bel Aire	24
Valley Center.....	27
Mulvane.....	30
Maize	33
Goddard	36
Rose Hill	39
Clearwater	42
Kechi	45
Cheney	48
Sedgwick.....	51
Colwich	54
Garden Plain	57
Andale.....	60
Mount Hope	63
Eastborough	66
Bentley.....	69
Viola	72

Introduction

Labor markets go beyond county and city lines. Every day, workers commute within various counties and cities, as well as across different jurisdictions. Certain jurisdictions within the Wichita Area Metropolitan Planning Organization (WAMPO) region have a comparative advantage in particular industries, as evidenced by the numbers of workers that commute to those areas each day. That is not to say that the communities those workers leave to commute are lacking in some way- they may have the advantage in available housing, recreational amenities, or other key economic factors.

This report compiles data about the locations of workers' primary (non-home) workplaces and residences. Together, these data provide an understanding of commuter flows, showing the interconnectedness of communities and the interchange of workers and services between areas. This helps to define and distinguish the Wichita metropolitan area from smaller stand-alone communities and other metropolitan and micropolitan areas in Kansas. Wichita is the clear hub of the WAMPO region, though the cities around it are growing in both residential appeal and job opportunities through the increasing number of industrial and commercial giants seeking out Wichita and its surrounding areas. Many of these cities focus on residents' quality of life by expanding residential areas and accompanying amenities.

Of further significance in commuting patterns are the schools in and around a municipality. The presence of a unified school district in a city indicates greater community infrastructure and quality of life—important factors for those who may choose either to both live and work in a particular city or to only live there. For example, some smaller or neighboring municipalities in the WAMPO region rely upon Wichita for education.

Note: The data presented in this report includes cities within the WAMPO region. The data source is the [U.S. Census Bureau, Center for Economic Studies, LEHD, OnTheMap](#) from 2015 to 2019 (the most recent year available as of July 2022), unless otherwise noted. This source used information from W2 tax forms, which may have some inaccuracies.

WAMPO Planning Boundary

Sedgwick County, which is entirely within the WAMPO region and accounts for most of its land area and population, is the second most populous county in Kansas and is home to the state's most populous city, Wichita. It is bordered by Butler and Sumner Counties (parts of which are in the WAMPO region), as well as Reno, Harvey, and Kingman counties (which are entirely outside the WAMPO region). One reason for commute flows out of Sedgwick County is employment at Butler County Community College in Butler County, Hutchinson Community College in Reno County, and Hesston College and Bethel College in Harvey County. Similarly, Wichita State University, Friends University, and Newman University in Sedgwick County create commuter flows into the county and into the WAMPO region from the five adjacent counties.


The cities in this report are presented in decreasing population order. Using US Census Bureau Decennial 2020 Data the following is a ranking of the largest to smallest municipalities in the WAMPO Region:

- | | | |
|--------------------------|------------------------|------------------------|
| 1. Wichita (397,532) | 9. Maize (5,735) | 17. Garden Plain (948) |
| 2. Derby (25,625) | 10. Goddard (5,084) | 18. Andale (941) |
| 3. Andover* (14,892) | 11. Rose Hill* (4,185) | 19. Mount Hope (806) |
| 4. Haysville (11,262) | 12. Clearwater (2,653) | 20. Eastborough (756) |
| 5. Park City (8,333) | 13. Kechi (2,217) | 21. Bentley (560) |
| 6. Bel Aire (8,262) | 14. Cheney (2,181) | 22. Viola (115) |
| 7. Valley Center (7,340) | 15. Sedgwick* (1,603) | |
| 8. Mulvane* (6,286) | 16. Colwich (1,455) | |


*Included in the WAMPO region but in (or partially in) different counties are Andover, which is entirely in Butler County, Rose Hill, which is in Butler and Sedgwick Counties, Mulvane, which is in Sumner and Sedgwick Counties, and the City of Sedgwick is split between Sedgwick and Harvey Counties).

For 2020, the U.S. Census Bureau estimated Sedgwick County's population to be 523,824 (not to be confused with the county's labor force, which is a subset of the population). In the same year, the mean travel time to work for workers aged 16+ was 19.3 minutes. Sedgwick County sees a regular inflow of 19,130 workers coming into the county from residences in the five adjacent counties, and a regular outflow of 10,561 workers who live in Sedgwick County and are employed in the other counties. Over half of those who commute into Sedgwick County from adjacent counties come from Butler County. However, of those who live in Sedgwick County and work elsewhere, there is a near even split between Butler, Sumner, Harvey, and Reno Counties, with a much smaller number commuting to Kingman County.

WAMPO Planning Boundary



Commuters by WAMPO Cities



Commuting Flows: Represents information about worker's residence location and workplace location

Internal: Represents workers who commute and live in the same city

Inflow: Represents workers who commute into a city for work

Outflow: Represents workers who commute out of a city for work

Commuters by WAMPO Cities

2019 Number of Commuters			
WAMPO Cities	Internal	Inflow	Outflow
Wichita	120,413	81,932	56,978
Derby	1,583	5,871	9,584
Andover	572	3,488	5,136
Park City	141	3,226	3,635
Haysville	402	2,087	4,390
Bel Aire	106	1,768	3,426
Valley Center	283	1,243	3,341
Maize	99	2,416	2,033
Goddard	129	1,673	2,298
Mulvane	205	1,047	2,734
Rose Hill	149	951	1,911
Kechi	10	356	1,209
Clearwater	186	454	1,099
Cheney	181	470	926
Colwich	34	730	644
Sedgwick	9	228	818
Andale	26	405	519
Garden Plain	7	192	363
Mt. Hope	14	103	393
Eastborough	10	32	361
Bentley	4	30	272
Viola	0	5	52

Commuting Flows: Represents information about worker's residence location and workplace location

Internal: Represents workers who commute and live in the same city

Inflow: Represents workers who commute into a city for work

Outflow: Represents workers who commute out of a city for work

Wichita



Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>



Wichita is the largest city in Kansas, the primary hub of the greater WAMPO area, and the county seat of Sedgwick County. Incorporated in 1870, it is the principal city of the greater Wichita metropolitan area. Wichita has the largest school district in Kansas and employees over 5,600 full-time employees. As of 2020, Wichita’s population was 397,532, of which approximately 67% are in the labor force¹. The mean travel time to work is 18.8 minutes.

It has been dubbed the “Air Capital of the World” because of the presence of various aircraft design and manufacturing facilities, such as Textron Aviation, Bombardier Learjet, Airbus, Spirit AeroSystems, as well as housing major airports such as Dwight D. Eisenhower National, Colonel James Jabara, Westport, Beech Factory, and Cessna Aircraft Field.


Wichita has the greatest number of residents who live and work in the city, at 120,413. 81,932 residents live in other cities both within and outside of the WAMPO area and commute to Wichita for work. 56,978 residents live in Wichita and work elsewhere. From 2015 compared to 2019, Wichita has seen an approximate 19% increase in the number of residents who commute to other cities for work.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	20,047 (16.6%)	12,731 (15.5%)	21,265 (37.3%)
Trade, Transportation, & Utilities	20,833 (17.3%)	18,604 (22.7%)	9,663 (17.0%)
All Other Services	79,533 (66.1%)	50,597 (61.8%)	26,050 (45.7%)

¹ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2079000&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Wichita



128,273	(63.4%)
37,287	(18.4%)
10,137	(5.0%)
26,648	(13.2%)

of workers
who work in
Wichita live

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their
place of
employment




132,419	(74.6%)
21,805	(12.3%)
4,704	(2.7%)
18,463	(10.4%)

of workers
who live in
Wichita work

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their
place of
residence



Where Workers Work Who Live in Wichita

Derby





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Derby was incorporated in 1903 but was originally named El Paso until 1956. McConnell Air Force Base is located between Wichita and Derby with a Wichita ZIP code, and many found a home in Derby when space on base became occupied. As of 2020, Derby’s population was 25,625, of which approximately 67% are in the labor force². The mean travel time to work is 22.2 minutes. Many jobs in the Derby area are based in either construction, retail, or real estate. It is due to these jobs that many of the residents both work and live in Derby. Derby supports home-based businesses and large manufacturing companies like BRG Precision. Derby is served by their own public school district, as well as two private schools.


Between 2015 and 2019, the highest number of people living and working in Derby peaked in 2016 and saw declines in 2017 and 2018. Derby has had an approximate 18% increase from 2015 to 2019 in the number of people living outside city limits and commuting to Derby for work. Approximately 3% of workers employed in the WAMPO region live in Derby. Additionally, approximately 2% of workers who live in the WAMPO region work in Derby.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	85 (5.4%)	248 (4.2%)	2,710 (28.3%)
Trade, Transportation, & Utilities	129 (8.1%)	1,578 (26.9%)	1,648 (17.2%)
All Other Services	1,369 (86.5%)	4,045 (68.9%)	5,226 (54.5%)


² US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2017800&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Derby




4,319 (57.9%)	of workers who work in Derby live	less than 10 miles	from their place of employment
1,876 (25.2%)		10 - 24 Miles	
413 (5.5%)		25 - 50 Miles	
846 (11.3%)		greater than 50 Miles	



5,447 (48.8%)	of workers who live in Derby work	less than 10 miles	from their place of residence
4,189 (37.5%)		10 - 24 Miles	
363 (3.3%)		25 - 50 Miles	
1,168 (10.5%)		greater than 50 Miles	

Where Workers Work Who Live in Derby

Andover





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Andover was incorporated in 1957. As of 2020, Andover’s population was 14,892, approximately 70% of which are in the labor force³. The mean travel time to work is 22.6 minutes. Surrounded by farmland, the city was devastated by an F5 tornado that forced the town to rebuild in 1991. Andover again experienced extensive damage from an F3 tornado in April 2022. Updated streets, sewers, and water lines encouraged fresh development. Andover is served by their own public school district and is also home to a branch campus of Butler Community College. Andover has placed a great emphasis on newer retail properties, education, and building residential properties for young families. Another job draw is Vornado Air, currently headquartered in Andover.


There are 572 residents who live and work in Andover. 5,136 residents live in Andover but commute to another city for work. There are 3,488 residents who live in another city but travel into Andover for work. From 2015 compared to 2019, Andover has had an approximate 8% increase in the number of people living and working in the city. Approximately 2% of workers employed in the WAMPO region live in Andover. Additionally, approximately 1% of workers who live in the WAMPO region work in Andover.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	33 (5.8%)	363 (10.4%)	1,110 (21.6%)
Trade, Transportation, & Utilities	40 (7.0%)	531 (15.2%)	832 (16.2%)
All Other Services	499 (87.2%)	2,594 (74.4%)	3,194 (62.2%)

³ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2001800&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Andover




2,248	55.4%	of workers who work in Andover live	less than 10 miles	from their place of employment
1,288	31.7%		10 – 24 Miles	
153	3.8%		25 – 50 Miles	
371	9.1%		greater than 50 Miles	



2,611	(45.7%)	of workers who live in Andover work	less than 10 miles	from their place of residence
2,309	(40.5%)		10 – 24 Miles	
165	(2.9%)		25 – 50 Miles	
623	(10.9%)		greater than 50 Miles	

Where Workers Work Who Live in Andover



Haysville





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Incorporated in 1951 and colloquially known as the “Peach Capital of Kansas,” for their historic peach orchard, Haysville has a population of 11,262 as of 2020. Haysville has approximate 60% labor force⁴. The mean travel time to work is 23.5 minutes. Like Andover, Haysville faced a destructive tornado in 1999 that damaged 150 homes and 27 businesses. Norland Plastics Co., a subsidiary of Teleflex, Inc. was among the facilities rebuilt since the tornado and is a major employer in the area. Haysville is served by their own public school district. Included in their school district is Campus High School, located in Wichita.

There are 402 residents who live and work in Haysville, but 4,390 residents who live in Haysville but work elsewhere. There are 2,087 residents who live outside of Haysville and travel to there for work. In comparing 2015 to 2019, Haysville has seen an approximate 11% increase in the number of people employed in the city but live outside city limits and commute to work.




Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	19 (4.7%)	322 (15.4%)	1,307 (29.8%)
Trade, Transportation, & Utilities	26 (6.5%)	143 (6.9%)	848 (19.3%)
All Other Services	357 (88.8%)	1,622 (77.7%)	2,235 (50.9%)

⁴ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2031125&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Haysville

1,605 (64.5%)	of workers who work in Haysville live	less than 10 miles	from their place of employment
605 (24.3%)		10 – 24 Miles	
85 (3.4%)		25 – 50 Miles	
194 (7.8%)		greater than 50 Miles	



3,038 (63.4%)	of workers who live in Haysville work	less than 10 miles	from their place of residence
1,029 (21.5%)		10 – 24 Miles	
203 (4.2%)		25 – 50 Miles	
522 (10.9%)		greater than 50 Miles	

Where Workers Work Who Live in Haysville

Park City





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Park City is one the newest city in the WAMPO region, which was incorporated in 1980. Park City is another municipality largely made up of commuters. As of 2020, Park City’s population was 8,333, of which approximately 74% are in the labor force⁵. The mean travel time to work is 20.5 minutes. Many of the workers are gainfully employed by recent boons to the city such as Crosswinds Casino, Hartman Arena, and an Amazon fulfillment center. The city does not have their own public school district, rather, students are split between the Wichita and Valley Center school districts.


There are 141 residents who live and work in Park City. 3,635 residents live in Park City but commute to another city for work. There are 3,226 residents who live in another city. From 2015 to 2019, Park City has had an approximate 5% increase in the number of people living and working in the city limits.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	32 (22.7%)	1,242 (38.5%)	837 (23.0%)
Trade, Transportation, & Utilities	48 (34.0%)	1,260 (39.1%)	665 (18.3%)
All Other Services	61 (43.3%)	724 (22.4%)	2,133 (58.7%)

⁵ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2054450&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Park City




45	57.7%
13	16.7%
11	14.1%
9	11.5%

of workers who
work in Park
City live

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their
place of
employment



31	56.4%
3	5.5%
6	10.9%
15	27.3%

of workers who live
in Park City work

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their
place of
residence

Where Workers Work Who Live in Park City

Bel Aire





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Bel Aire is another newer city in this region and was incorporated in 1980. As of 2020, Bel Aire’s population was 8,262, of which approximately 67% are in the labor force⁶. The mean travel time to work is 17.2 minutes. The city does not have their own public school district. They are served by both the Wichita and Towanda school districts.


There are 106 residents who live and work in Bel Aire. 3,426 residents live in Bel Aire but commute to another city for work. There are 1,768 residents who live in another city but travel into Bel Aire for work. From 2015 compared to 2019, the city has had an approximate 21% increase in the number of people commuting from outside the city limits to Bel Aire for work.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	13 (12.3%)	325 (15.5%)	663 (19.4%)
Trade, Transportation, & Utilities	14 (13.2%)	381 (22.7%)	484 (14.1%)
All Other Services	79 (74.5%)	1,062 (61.8%)	2,279 (66.5%)

⁶ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2005337&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Bel Aire



1,084	57.8%
512	27.3%
64	3.4%
214	11.4%

of workers who work in Bel Aire live

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of employment




2,490	70.5%
588	16.6%
100	2.8%
354	10.0%

of workers who live in Bel Aire work

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of residence



Where Workers Work Who Live in Bel Aire

Valley Center





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

The city of Valley Center was first incorporated in 1885 and conveniently located near I-135, US-81, and K-15. As of 2020, Valley Center’s population was 7,340, of which approximately 69% are in the labor force⁷. The mean travel time to work is 23.5 minutes. The Valley Center Public School District and alternative school serves communities from all over the WAMPO area, including Park City, Kechi, and Wichita.


There are 283 residents who both live and work in Valley Center, but the majority of people live in Valley Center and commute to another city. 3,341 residents live in Valley Center but commute to another city for work. There are 1,243 residents who live in another city but travel into Valley Center for work. From 2015 compared to 2019, Valley Center had an approximate 8% increase in the number of residents who commute to other cities for work.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	42 (14.8%)	343 (27.6%)	843 (25.2%)
Trade, Transportation, & Utilities	34 (12.0%)	220 (17.7%)	609 (18.2%)
All Other Services	207 (731%)	680 (54.7%)	1,889 (56.5%)

⁷ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2073250&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Valley Center



913	59.8%
427	28.0%
89	5.8%
97	6.4%

of workers who work in Valley Center live

less than 10 miles
10 - 24 Miles
25 - 50 Miles
greater than 50 Miles

from their place of employment




1,257	34.7%
1,820	50.2%
189	5.2%
358	9.9%

of workers who live in Valley Center work

less than 10 miles
10 - 24 Miles
25 - 50 Miles
greater than 50 Miles

from their place of residence



Where Workers Work Who Live in Valley Center

Mulvane





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Mulvane is the second oldest city in the region, being first incorporated in 1883. When it was founded, it was located at the junction of five Santa Fe rail lines and is still a convenient point today, south of Wichita. As of 2020, Mulvane’s population was 6,286, of which approximately 68% are in the labor force⁸. The mean travel time to work is 19.8 minutes. Mulvane is served by their own public school district. The Kansas Star Casino and a Cowley County Community College satellite campus are located in Mulvane.

There are 205 residents who choose to live and work in Mulvane. There are 1,047 people who live outside of Mulvane and travel there to work. Additionally, 2,734 residents commute for work outside Mulvane. From 2015 compared to 2019, there was an approximate 18% increase in the number of people living and working in Mulvane. From 2017 to 2019, Mulvane has seen a decrease in the number of people who live outside the city limits that commute to Mulvane for work.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	12 (5.9%)	97 (9.3%)	756 (27.7%)
Trade, Transportation, & Utilities	9 (4.4%)	126 (12.0%)	445 (16.3%)
All Other Services	184 (89.8%)	824 (78.7%)	1,533 (56.1%)

⁸ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2049100&tid=ACSDP5Y2020.DP03>





Where Workers Live Who Work in Mulvane

913	59.8%
427	28.0%
89	5.8%
97	6.4%

of workers who work in Mulvane live

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of employment



1,257	34.7%
1,820	50.2%
189	5.2%
358	9.9%

of workers who live in Mulvane work

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of residence

Where Workers Work Who Live in Mulvane

Maize





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

The city of Maize was first incorporated in 1915. Growth really hit the area in the 1950s and has continued rapidly in recent years as Wichita expands further northwest. As of 2020, Maize’s population was 5,735, of which approximately 68% are in the labor force⁹. The mean travel time to work is 21.9 minutes. Maize is served by their own public school district, including an alternative, nontraditional school.


There are 99 residents who live and work in Maize, that is an approximate 32% increase in 2019 compared to 2015. 2,033 residents live in Maize but commute to another city for work. There are 2,416 residents who live in another city but travel into Maize for work, that is an approximate 36% increase in 2019 compared to 2015.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	11 (11.1%)	591 (245%)	465 (22.9%)
Trade, Transportation, & Utilities	1 (1.0%)	102 (4.2%)	347 (17.1%)
All Other Services	87 (87.9%)	1,723 (71.3%)	1,221 (60.1%)

⁹US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2044200&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Maize




1,608	63.9%
624	24.8%
107	4.3%
176	7.0%

of workers who work in Maize live

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of employment



1,255	58.9%
621	29.1%
92	4.3%
164	7.7%

of workers who live in Maize work

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of residence

Where Workers Work Who Live in Maize

Goddard





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Goddard is also one of the older municipalities in the region and was first founded in 1883 and incorporated in 1910. As of 2020, Goddard’s population was 5,084 of which approximately 69% are in the labor force¹⁰. The mean travel time to work is 20.5 minutes. Wichita has expanded westward; the town has changed from a rural agricultural community into more of a true city. Manufacturing, educational services, health care, and social assistance are the main labor draws for Goddard. Because US-54 and US-400 run concurrently through Goddard, it is easy for citizens to flow in and out of the city. Goddard is served by their own public school district. There is also a Catholic private school in the city.


There are 129 residents who live and work in Goddard, that is an approximate 30% decrease from 2019 compared to 2015. There are 1,673 residents who live in another city but travel into Goddard for work. From 2017 to 2019, Goddard has seen an increase in the number of people who reside outside the city limits and commute to Goddard for work.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	5 (3.9%)	62 (3.7%)	615 (26.8%)
Trade, Transportation, & Utilities	15 (11.6%)	319 (19.1%)	426 (18.5%)
All Other Services	109 (84.5%)	1,292 (77.2%)	1,257 (54.7%)


¹⁰ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2026725&tid=ACSDP5Y2020.DP03>




Where Workers Live Who Work in Goddard



988	54.8%	of workers who work in Goddard live	less than 10 miles	from their place of employment
559	31.0%		10 – 24 Miles	
119	6.6%		25 – 50 Miles	
136	7.5%		greater than 50 Miles	



932	38.4%	of workers who live in Goddard work	less than 10 miles	from their place of residence
1,110	45.7%		10 – 24 Miles	
134	5.5%		25 – 50 Miles	
251	10.3%		greater than 50 Miles	



Where Workers Work Who Live in Goddard

Rose Hill





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Rose Hill is located in Butler County and was incorporated in 1955. As of 2020, Rose Hill’s population was 4,185, of which approximately 69% are in the labor force.¹¹ The mean travel time to work is 24.8 minutes. Cook Airfield is a recreational airport located nearby and is a major draw for the city. The community has their own public school district.


There are 149 residents who live and work in Rose Hill, but nearly half of the population (1,911 residents) travel to another city for work. There are 951 people who live in another city and travel to Rose Hill, which is an approximate 10% increase in 2019 as compared to 2015.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	12 (8.1%)	88 (9.3%)	593 (31.0%)
Trade, Transportation, & Utilities	3 (2.0%)	64 (6.7%)	311 (16.3%)
All Other Services	134 (89.9%)	799 (84.0%)	1,007 (52.7%)


¹¹ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2061250&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Rose Hill



433	39.4%	of workers who work in Rose Hill live	less than 10 miles	from their place of employment
481	43.7%		10 – 24 Miles	
60	5.5%		25 – 50 Miles	
126	11.5%		greater than 50 Miles	



648	31.5%	of workers who live in Rose Hill work	less than 10 miles	from their place of residence
1,149	55.8%		10 – 24 Miles	
38	1.8%		25 – 50 Miles	
225	10.9%		greater than 50 Miles	

Where Workers Work Who Live in Rose Hill

Clearwater





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Clearwater is one of the older cities in Sedgwick County and was incorporated in 1885. On the Chisholm Trail, the city began as a small trading post and has consistently increased in population ever since. Clearwater is served by their own public school district. As of 2020, Clearwater’s population was 2,653, of which approximately 67% are in the labor force.¹² The mean travel time to work is 24.9 minutes.


There are 186 residents who live and work in Clearwater. 1,099 residents live in Clearwater but commute to another city for work. There are 454 residents who live in another city but travel into Clearwater for work, which is an approximate 9% decrease in 2019 compared to 2015.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	24 (12.9%)	38 (8.4%)	336 (30.6%)
Trade, Transportation, & Utilities	14 (7.5%)	49 (10.8%)	199 (18.1%)
All Other Services	148 (79.6%)	367 (80.8%)	564 (51.3%)

¹² US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2013925&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Clearwater




286	44.7%	of workers who work in Clearwater live	less than 10 miles	from their place of employment
278	43.4%		10 – 24 Miles	
24	3.8%		25 – 50 Miles	
52	8.1%		greater than 50 Miles	



300	23.3%	of workers who live in Clearwater work	less than 10 miles	from their place of residence
820	63.8%		10 – 24 Miles	
54	4.2%		25 – 50 Miles	
111	8.6%		greater than 50 Miles	

Where Workers Work Who Live in Clearwater



Kechi





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Kechi is a city located to the northeast of Wichita and was incorporated in 1957. Kechi is served by both the Wichita and the Valley Center Public School Districts. The city is 15 minutes from the Dwight D. Eisenhower National Airport and Downtown Wichita. As of 2020, Kechi’s population was 2,217, of which approximately 71% are in the labor force.¹³ The mean travel time to work is 20.5 minutes.


There are 10 residents who live and work in Kechi. 1,209 residents live in Kechi but commute to another city for work, that is an approximate 12% increase from 2019 compared to 2015. There are 356 residents who live in another city but travel to Kechi for work.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	5 (50.0%)	242 (68.0%)	268 (22.2%)
Trade, Transportation, & Utilities	3 (30.0%)	45 (12.6%)	213 (17.6%)
All Other Services	2 (20.0%)	69 (19.4%)	728 (60.2%)

¹³ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2036225&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Kechi




167	45.6%
143	39.1%
7	1.9%
49	13.4%

of workers who work in Kechi live

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of employment



661	54.2%
415	34.0%
49	4.0%
94	7.7%


of workers who live in Kechi work

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of residence

Where Workers Work Who Live in Kechi

Cheney





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

The City of Cheney was first founded in 1883 as a station and shipping point on the Santa Fe Railway and Cheney State Park. The Cheney Reservoir has since become a popular recreation destination for many in the area. Cheney is served by their own public school district, operating. As of 2020, Cheney's population was 2,181, of which approximately 63% are in the labor force.¹⁴ The mean travel time to work is 20.9 minutes.


There are 181 residents who live and work in Cheney. 926 residents live in Cheney but commute to another city for work, that is an approximate 10% increase in 2019 compared to 2015. There are 470 residents who live in another city but travel to Cheney for work.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	17 (9.4%)	49 (10.4%)	289 (31.2%)
Trade, Transportation, & Utilities	36 (19.9%)	151 (32.1%)	160 (17.3%)
All Other Services	128 (70.7%)	270 (57.4%)	477 (51.5%)


¹⁴ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2012775&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Cheney




277	42.5%	of workers who work in Cheney live	less than 10 miles	from their place of employment
238	36.6%		10 – 24 Miles	
82	12.6%		25 – 50 Miles	
54	8.3%		greater than 50 Miles	



218	19.7%	of workers who live in Cheney work	less than 10 miles	from their place of residence
467	42.2%		10 – 24 Miles	
295	26.6%		25 – 50 Miles	
127	11.5%		greater than 50 Miles	

Where Workers Work Who Live in Cheney



Sedgwick




Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

The city of Sedgwick lies within both Harvey and Sedgwick Counties and calls itself “a little town with a big heart.” Sedgwick is one of the earliest incorporated cities, second to Wichita, in the WAMPO region and was incorporated in 1872. The city positions itself to have the pleasures of small-town living but close to big city jobs—ideal for commuters. Sedgwick is served by their own public school district. As of 2020, Sedgwick’s population was 1,603, of which approximately 63% are in the labor force.¹⁵ The mean travel time to work is 26.1 minutes.


There are 9 residents who live and work in Sedgwick, that is an approximate 60% decrease in 2019 compared to 2015. Sedgwick has seen an approximate 13% increase, from 2019 compared to 2015, in the number of residents that live in Sedgwick but commute to another city for work. There are 228 residents who live in another city but travel to Sedgwick for work, that is an approximate 36% decrease in 2019 compared to 2015.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	1 (11.1%)	53 (23.2%)	221 (27.0%)
Trade, Transportation, & Utilities	2 (22.2%)	45 (19.7%)	135 (16.5%)
All Other Services	6 (66.7%)	130 (57.0%)	462 (56.5%)

¹⁵ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2063800&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Sedgwick




87	36.7%	of workers who work in Sedgwick live	less than 10 miles	from their place of employment
100	42.2%		10 - 24 Miles	
24	10.1%		25 - 50 Miles	
26	11.0%		greater than 50 Miles	




189	22.9%	of workers who live in Sedgwick work	less than 10 miles	from their place of residence
465	56.2%		10 - 24 Miles	
88	10.6%		25 - 50 Miles	
85	10.3%		greater than 50 Miles	

Where Workers Work Who Live in Sedgwick



Colwich





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

A rural-suburban city, Colwich has faced continued population expansion and economic growth. Colwich was founded in 1887 and is located approximately 5-miles northwest of Wichita. Colwich does not have their own school district. They are served by the Renwick Public School District, which supports Andale and Garden Plain, as well. As of 2020, Colwich’s population was 1,455, of which approximately 74% are in the labor force.¹⁶ The mean travel time to work is 20.1 minutes.


There are 34 residents who live and work in Colwich. 644 residents live in Colwich but commute to another city for work. There are 730 residents who live in another city but travel into Colwich for work, that is an approximate 38% increase in 2019 compared to 2015.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	2 (5.9%)	40 (5.5%)	162 (25.2%)
Trade, Transportation, & Utilities	3 (8.8%)	42 (5.8%)	110 (17.1%)
All Other Services	29 (85.3%)	648 (88.8%)	372 (57.8%)

¹⁶ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2015100&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Colwich



389	50.9%
314	41.1%
31	4.1%
30	3.9%

of workers
who work in
Colwich live

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their
place of
employment




211	31.1%
354	52.2%
32	4.7%
81	11.9%

of workers
who live in
Colwich work

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their
place of
residence



Where Workers Work Who Live in Colwich

Garden Plain





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Located west of Wichita, Garden Plain was founded as a junction between Wichita and Kingman on the Wichita and Western Railroad. Since its incorporation in 1903, the city has seen an increase in population because of its family-oriented community. Garden Plain is served by the Renwick Public School District, which supports Andale and Colwich as well. As of 2020, Garden Plain’s population was 948, of which approximately 77% are in the labor force.¹⁷ The mean travel time to work is 24.6 minutes.


There are 7 residents who live and work in Garden Plain, that is an approximate 36% decrease in 2019 compared to 2015. 363 residents live in Garden Plain but commute to another city for work, which is an approximate 16% decrease in 2019 compared to 2015. There are 192 residents who live in another city but travel into Garden Plain for work, an approximate 68% increase in 2019 compared to 2015.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	3 (42.9%)	30 (15.6%)	88 (24.2%)
Trade, Transportation, & Utilities	1 (14.3%)	107 (55.7%)	53 (14.6%)
All Other Services	3 (42.9%)	55 (28.6%)	222 (61.2%)


¹⁷ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2025375&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Garden Plain



65	32.7%	of workers who work in Garden Plain live	less than 10 miles	from their place of employment
88	44.2%		10 – 24 Miles	
25	12.6%		25 – 50 Miles	
21	10.6%		greater than 50 Miles	



82	22.2%	of workers who live in Garden Plain work	less than 10 miles	from their place of residence
214	57.8%		10 – 24 Miles	
36	9.7%		25 – 50 Miles	
38	10.3%		greater than 50 Miles	

Where Workers Work Who Live in Garden Plain

Andale

Population Rank
18th





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Andale was founded as a station and shipping point on the Missouri Pacific Railroad in the 1880s and incorporated in 1901. Andale is supported by the Renwick Public School District, which supports Garden Plain and Colwich, as well. As of 2020, Andale’s population was 941, of which approximately 74% are in the labor force.¹⁸ The mean travel time to work is 25.2 minutes.


There are 26 residents who live and work in Andale. 519 residents live in Andale but commute to another city for work, that is an approximate 11% increase in 2019 compared to 2015. There are 405 residents who live in another city but travel into Andale for work, that is an approximate 13% increase in 2019 compared to 2015.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	1 (3.8%)	7 (1.7%)	117 (22.5%)
Trade, Transportation, & Utilities	0 (0.0%)	57 (14.1%)	79 (15.2%)
All Other Services	25 (96.2%)	341 (84.2%)	323 (62.2%)

¹⁸ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2001775&tid=ACSDP5Y2020.DP03>




Where Workers Live Who Work in Andale



198	45.9%	of workers who work in Andale live	less than 10 miles	from their place of employment
195	45.2%		10 – 24 Miles	
17	3.9%		25 – 50 Miles	
21	4.9%		greater than 50 Miles	




104	19.1%	of workers who live in Andale work	less than 10 miles	from their place of residence
366	67.2%		10 – 24 Miles	
30	5.5%		25 – 50 Miles	
45	8.3%		greater than 50 Miles	



Where Workers Work Who Live in Andale

Mount Hope





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Mount Hope was founded in 1874 and incorporated in 1887. They are served by the Haven Public School District in Reno County, outside of the WAMPO area. As of 2020, Mount Hope’s population was 806, of which approximately 65% are in the labor force.¹⁹ The mean travel time to work is 30.0 minutes.


There are 14 residents who live and work in Mount Hope. There are 393 residents live in Mount Hope but commute to another city for work. There are 103 residents who live in another city but travel to Mount Hope for work, and that is an approximate 7% decrease in 2019 compared to 2015.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	1 (7.1%)	9 (8.7%)	95 (24.2%)
Trade, Transportation, & Utilities	1 (7.1%)	13 (12.6%)	72 (18.3%)
All Other Services	12 (85.7%)	81 (78.6%)	226 (57.5%)

¹⁹ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2048900&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Mount Hope




38	32.5%
53	45.3%
8	6.8%
18	15.4%

of workers who work in Mount Hope live

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of employment



57	14.0%
255	62.7%
59	14.5%
36	8.8%

of workers who live in Mount Hope work

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of residence

Where Workers Work Who Live in Mount Hope

Eastborough



Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>


Eastborough was incorporated in 1937 and is an enclave of the city of Wichita, dubbed “Wichita’s finest residential section.”²⁰ Being surrounded by Wichita, Eastborough does not have their own school district, instead sending their students to the Wichita Public School District or Wichita area private schools. As of 2020, Eastborough’s population was 756, of which approximately 63% are in the labor force.²¹ The mean travel time to work is 14.0 minutes.

There are 10 residents who live and work in Eastborough. 361 residents live in Eastborough but commute to another city for work. There are 32 residents who live in another city but travel into Eastborough for work.


Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	2 (20.0%)	9 (28.1%)	62 (17.2%)
Trade, Transportation, & Utilities	2 (20.0%)	1 (3.1%)	52 (14.4%)
All Other Services	6 (60.0%)	22 (68.8%)	247 (68.4%)

²⁰ City of EastBorough Newsletters, www.eastborough-ks.gov/history/history.php

²¹ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2019300&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Eastborough



26	61.9%
11	26.2%
1	2.4%
4	9.5%

of workers who work in Eastborough live

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of employment




296	79.8%
34	9.2%
4	1.1%
37	10.0%

of workers who live in Eastborough work


less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their place of residence



Where Workers Work Who Live in Eastborough

Bentley




Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Bentley was founded as a depot on the Kansas Midland Railway in 1888 but was not incorporated until 1959. The rail line has since been abandoned but the city is growing as a residential destination. Bentley does not have their own school district. They are served by the Halstead Public School District in Harvey County, outside of WAMPO boundaries. As of 2020, Bentley’s population was 560, of which approximately 58% are in the labor force.²² The mean travel time to work is 24.1 minutes.


There are 4 residents who live and work in Bentley, which is an approximate 67% decrease in 2019 compared to 2015. 272 residents live in Bentley but commute to another city for work. There are 30 residents who live in another city but travel into Bentley for work, an approximate 40% decrease in 2019 compared to 2015.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	0 (0.0%)	0 (0.0%)	64 (23.5%)
Trade, Transportation, & Utilities	0 (0.0%)	0 (0.0%)	45 (16.5%)
All Other Services	4 (100.0%)	30 (100.0%)	163 (59.9%)

²² US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2006125&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Bentley




16	47.1%
12	35.3%
2	5.9%
4	11.8%

of workers
who work in
Bentley live

less than 10 miles
10 - 24 Miles
25 - 50 Miles
greater than 50 Miles

from their
place of
employment



42	15.2%
183	66.3%
26	9.4%
25	9.1%



of workers who
live in Bentley
work

less than 10 miles
10 - 24 Miles
25 - 50 Miles
greater than 50 Miles

from their
place of
residence

Where Workers Work Who Live in Bentley

Viola





Source: U.S. Census Bureau, Center for Economic Studies, LEHD. Accessed in July 2022 at <https://onthemap.ces.census.gov/>

Viola was first founded in 1870 as a town off the Englewood branch of the Santa Fe railroad but has faced a decreasing population since the late nineteenth century. The city was incorporated in 1909. Viola is home to Lake Afton, a popular recreation spot. Viola does not have their own school district. Instead, the community is served by the Conway Springs Public School District in Sumner County which is outside of WAMPO boundaries. As of 2020, Viola’s population was 115, of which approximately 72% are in the labor force.²³ The mean travel time to work is 22.8 minutes.


As of 2019, there were a total of 128 residents in the city. There are no residents who live and work in Viola. 52 residents live in Viola but commute to another city for work, which is an approximate 13% decrease in 2019 compared to 2015. There are 5 residents who live in another city but travel to Viola for work.

Industry Class (2019)	Internal	Inflow	Outflow
Goods Producing	0 (-)	0 (0.0%)	18 (34.6%)
Trade, Transportation, & Utilities	0 (-)	0 (0.0%)	9 (17.3%)
All Other Services	0 (-)	5 (100.0%)	25 (48.1%)

²³ US Census 2020: ACS 5-Year Estimates Data Profiles
Retrieved from: <https://data.census.gov/cedsci/table?g=1600000US2074025&tid=ACSDP5Y2020.DP03>



Where Workers Live Who Work in Viola



2	40.0%
3	60.0%
0	0.0%
0	0.0%

of workers
who work in
Viola live

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their
place of
employment



2	3.8%
38	73.1%
5	9.6%
7	13.5%

of workers who
live in Viola work

less than 10 miles
10 – 24 Miles
25 – 50 Miles
greater than 50 Miles

from their
place of
residence

Where Workers Work Who Live in Viola

